## **Mikhail Kostin**

Beam Injection Dump

Fermilab

October 6, 2004



## Model

- The system is azimuthally symmetric for simplicity.
- 1 m or 0.3 m in the transverse direction provide an order of magnitude dose reduction. Beam dumps for 20 kW and 40 kW are almost same.
- Beam intensity:

1 GeV = 
$$1.6 \times 10^{-10}$$
 J; 8 GeV =  $12.8 \times 10^{-10}$  J  
N<sub>p</sub>= $40,000$  W /  $(12.8 \times 10^{-10})$  =  $3.125 \times 10^{13}$  proton/sec


- Fermilab soil is wet dirt with  $\rho = 2.24 \text{ g/cm}^3$
- Central part is a block of steel, some part can be replaced with concrete.
- 1 m pass around the dump (for firemen)
- 1'-thick concrete wall

## Design Criteria

- Promt Dose on surface (occupied areas)
  - $\leq$  0.05 mrem/hr for normal operation
  - $\leq 1.00$  mrem/hr for accident

Design driven by normal operation, not accident.

- Hands-on maintenance dose ≤ 100 mrem/hr=1 mSv/hr
- Sump water activation  $\leq 2000 \text{ star/cm}^3/\text{sec.}$ Water activation limit for MIPP (E907) is  $5.96 \times 10^{10} \text{ star/year/cm}^3$ . That corresponds to  $0.9536 \times 10^{-10} \text{ star/cm}^3/\text{1}\text{proton}$  for the 'standard Fermilab year' (2  $\times 10^7 \text{ sec}$ ). Star density for hadrons with E  $\geq 50 \text{ MeV}$ .



Fermilab




Figure 2: Prompt Dose.

One can not simulate fast many meters of soil (too long). Need an estimate. For 5 m of soil and concrete one expects 10<sup>5</sup> prompt dose rate reduction.




Figure 3: Residual Dose.




Figure 4: Star density.

Star Density<sub>max</sub> =  $(8.114 \pm 3.734) \times 10^{-12}$ 



Estimate for Dump Transverse Size

'Minimal Dump':

- $\bullet$  steel 3.5 m  $\times$  3.5 m driven by star density, not by residual dose
- 8 m of soil, less if the area fenced as "Radiation Area".